Warringah Crane and Transport Service Pty Ltd

ABN 12 000 296 257

38 Myoora Rd., Terrey Hills 2084

Tel: (02) 9479 7300 Fax: (02) 9986 3677

CARRIERS-INDUSTRIAL REMOVALISTS-LIFTING CONTRACTORS



SAFE WORK METHOD STATEMENT (SWMS) (Job Safety Analysis Worksheet - Scope of Works)

DESCRIPTION OF WORK SPECIFIC TO THE ACTIVITY / TASK BEING UNDERTAKEN:

THIS PAGE TO BE COMPLETED ON SWMS RESPONSE SHEET

This Safe Work Method Statement is submited to:

COMPANY: CONTACT NAME / DEPARTMENT:

PHONE NUMBER:

This Safe Work Method Statement was reviewed by:

NAME:	POSITION:
SIGNATURE:	DATE:
PHONE NUMBER:	MOBILE NUMBER:

Responsible person who will implement, review, supervise, oversee, approve & inspect workplace, plant, tools, protective measures & equipment on Contractors behalf).

NAME:	POSITION:
SIGNATURE:	DATE:
PHONE NUMBER:	MOBILE NUMBER:
	This SWMS has been developed and authorised by:

This Swivis has been developed and authorised by:		
Name: John Clark	Date:	29th October 2015
Position: Manager	Phone:	(02)9479 7300
Version: 3.03 29/10/2015		

CHECKLIST OF ITEMS THAT MAY BE REQUIRED FOR THIS WORK ACTIVITY						
WORKCOVER APPROVALS/ CERTIFICATES ote: Design and Item Registration for certain pla	NSW OHS Induction for Construction Work WorkCover Plant Registration Work Cover Item Registration					
LIST OF RELEVANT LEGISLATION APPLICABLE CODES OF PRACTICE OR ADDITIONAL REFERENCES AS REQUIRED	Work Health and Safety Act 2011 Work Health and Safety Regulations WorkCoverCoP Work Near Overhead Powerlines WorkCoverCoP Moving Plant on Construction sites National Code of Practice Manual handling AS 2550:2002, Cranes Hoists and Winches					
COMMUNICATION & CONSULTATION	Regularly consults with its employees and contractors on OH&S by way of OH&S Committees, Toolbox Meetings and regular written communications. This Safe Work Method Statement was developed using these methods of communication & consultation. Any suggested improvements or issues with this SWMS should be reported to your supervisor and passed on to Head Office, this will allow for a process of continuous improvement in safety.					
MAINTENANCE CHECKS	Daily inspections and long book completed Annual inspection Major inspection after 10 years					

Plant, Equipment & Tools To				MSDS			Potential Hazard	Risk		
Be	Used	Tick	Hazardo	ous Substances	available <i>Tick</i>	Itemise PPE Used	Tick	Review Risks	Class	
Ste	o Ladder		No hazardous used	Substances		Hard Hat if required		Fall from ladder		
Lift	ng Equipment					Safety Boots Gloves - As required Safety Glasses	required Fall from scaffold es Contact with electricity Falling Objects Collapse			
		How Like	ly is it to be th	at Bad?			ivities are sc	Slip, trips and falls Manual handling Exposure to noise Struck by moving plant Cuts Other: List <i>pe of Works</i> ored for risks associated with		
f Damage	What Damage could it cause?	Very Likely Could happen anytime	Likely Could happen sometimes	Unlikely Could happen, but only rarely	Very Unlikely Could happen, but probably never will	1. Step by step sequen start to finish	ce of the tas	reduce the risk to the lowest ks in carrying out the work fi the risk to health and safety	•	
and Likelihood of	Death or Permanent disability	1	1	2	3	 Rating of the risk (fr The safety controls reduce the risk to th 	that will be i	mplemented to eliminate or		
ks and Lik	Long term illness or serious injury		2	3	4	NOTE: If a hazard i	s rated 1, 2 o	have been implemented or 3 action must be taken r rol is adequate to reduce th a	2	
Health Risks	Medical attention & several days off work	2	3	4	5	hazard to at least 4 6. Insert the name or t ensuring these cont undertaken.	itle of the pe			

Nid nee	^{ed} 3 4 5 6
---------	------------------------------

S T P	Job Step Break the job down into steps, Outline each task to do the job	Hazards Identification Identify any potential hazards associated with each job step. Access any risks that could lead to an incident or lead to an adverse environmental impact and rate each risk accordingly	Risk Class	Controls Implemented Using the previous two columns as a guide, decide what actions are necessary to eliminate or minimise the hazards that could lead to an accident, injury or occupational illness or environmental impact. Note: Indicate new risk rating after controls used - that the resulting risk rating must be reduced to between 4 - 6.	Risk Class	Person Responsible
1	Delivery to client site	Vehicle / pedestrian collision	4	 Drive safely Licensed driver Obey signage / road rules 	6	Operator
2	Arrive at destination - Park on road or site & walk in to Site & Locate site office	 Site rules not followed Site Conditions Poor walking surfaces Traffic, Other workers/activities. Blind corners, penetrations Collison with personnel or plant 	1	Wear safety boots Be alert to site hazards Obey site signage 10km speed limit Flashing light to be fitted & switched on upon entering site Ground crew to stay clear of mobile plant High visible clothing to be worn Site conditions to be assessed prior to entry		Operator/Dogman
3	Site inductions and issuing of PPE for the task	 Inadequate training, consultation, planning and improvisation 	1	 A site specific induction to be carried out by the Principle contractor must be conducted to ensure the OH&S policies of the building site are provided and educated to all personnel. A second induction to be provided by Warringah Cranes to ensure the procedures nominated in SWMS are understood and implemented. All personnel's PPE allocation will be assessed and reissued if required. 	6	Principle contractor / Operator / Dogman
4	Establish scope of work and plan set-up, job risk assessment to be completed and signed by crane operator and site forman	 Poor walking surfaces Setting up in wrong spot Collision with worker or general public Collision with other vehicles 	5	 Wear safety boots Be alert to site hazards Supervision consultation / talk to foreman so as to ascertain what tasks have to be completed. Conduct risk assessment before starting on site, assess traffic conditions and proximity to other workers and general public. Principal contractor to provide traffic control, adhere to the traffic management plan Demarcate the crane operating area with traffic cones 	6	Operator & Dogman Site Foreman
5	Complete Driver Log Book	Daily checks not done	6	Complete all daily check prior to operations	6	Operator
6	Assess ground conditions (stability)	 Underground services Walking / working surface 	3	 Talk to site officials to ascertain in any underground services may interfere with your planned set up e.g. Telstra, Gas, Electricial Wear safety boots Larger outrigger pads 	6	Operator & Dogman Site Supervisor

S T P	Job Step Break the job down into steps, Outline each task to do the job	Hazards Identification Identify any potential hazards associated with each job step. Access any risks that could lead to an incident or lead to an adverse environmental impact and rate each risk accordingly	Risk Class	Controls Implemented Using the previous two columns as a guide, decide what actions are necessary to eliminate or minimise the hazards that could lead to an accident, injury or occupational illness or environmental impact. Note: Indicate new risk rating after controls used - that the resulting risk rating must be reduced to between 4 - 6.	Risk Class	Person Responsible
7	Position Crane for lifts/s	 Collisons Poor walking surfaces Traffic, Other workers / activities, blind corners, penetrations 	2	 Visually check for overhead & surrounding dangers/ electrical and static objects (scaffold etc) Ground crew to stay clear of mobile plant High visible clothing to be worn Wear safety boots Be alert to site hazards Place bunting tape or traffic cones around crane slew area Reverse Beeper fitted and working on machines 	6	Operator/Dogman
8	Extend Outriggers	Poor clearanceManual handling	3	Check to make sure enough space to extend outriggers Keep fingers clear	6	Oerator & Dogman
9	Pack Outriggers	 Packing failure if not correctly stacked Manual handling 	3	 Packing procedure as per calculations & ground condition Safe manual handling techniques Assess the size and weight of the object and the distance that the object is to be moved Identify all slip trip hazards Bend knees, have a straight back and keep the load as close to your body as possible when lifting 	5	Principle contractor / Operator / Dogman
10	Level crane and set up handling techniques	 Crane could slip off packing if not level Crane does not lift true to loac capacity specific by crane load chart 	3	 Ensure equal pressure on all outriggers, crane is level & packing level 	5	Operator/Dogman
11	Attach Lifting gear to hook, establish boom length and position to required area	Poor clearanceManual handling	1	 Be alert to hook position Use safe manual handling techniques (refer to step 9) Visual inspection of lifting gear 	5	Oerator & Dogman
12	Fit counterweights from truck to crane or crane to truck (All Terrain Machines)	 Collisions Manual handling Crushing appendages Failure of lifting gear Mechanical failure Communication 	1	 12 monthly certification and daily checks on lifting gear Slung by dogman Sign off on lift and radius chart Daily checks and service records to be completed Communication radios Visually check for surrounding dangers Safe manual handling techniques (refer to step 9) Keep arms, legs, hands etc clear of crush points 	6	Operator & Dogman

S T E P	Job Step Break the job down into steps Outline each task to do the job.	Hazards Identification Identify any potential hazards associated with each job step. Access any risks that could lead to an incident or lead to an adverse environmental impact and rate each risk accordingly		Controls Implemented Using the previous two columns as a guide, decide what actions are necessary to eliminate or minimise the hazards that could lead to an accident, injury or occupational illness or environmental impact. Note: Indicate new risk rating after controls used - that the resulting risk rating must be reduced to between 4 - 6.	Risk Class	Person Responsible
13	Needle/fly installation/ decommission and wire rope installation	 Incorrect setup Failure of lifting gear Communication 	1	 Be alert to hook position Use safe manual handling techniques (refer to step 9) 12 monthly certification erection/dismantle as per manufactures specs 	6	Operator/Dogman
14	Set up around in close proximity to electrical power lines	Contact with power lines	1	Check to make sure enough space to extend outriggers Keep fingers clear	6	Oerator & Dogman
15	Check lift weight and computer limits	Mechanical failureLifting gear failure	1	 Training and experience Check equipment Certification Daily check 	5	Operator / Dogman
16	Using ladders for access or assist in slinging loads	Unsafe use of ladders • ladder damaged • wrong type of ladder for the task • standing higher than the 3rd top rung • over stretching	2	 Use appropriate sized ladder All ladders used must: conform to the Australian Standard and be of industrial grade quality with a minimum load rating of 120kg be suitable for there intended use be inspected for damage before use - damaged or faulty ladders are not to be used be set up on a clean surface free from debris or material Always have 3 points of contact climbing up or down the ladder Never climb higher than the 3rd rung from the top Never over stretch and work within the confines of the ladder 	6	

S T P	Job Step Break the job down into steps Outline each task to do the job.	Hazards Identification Identify any potential hazards associated with each job step. Access any risks that could lead to an incident or lead to an adverse environmental impact and rate each risk accordingly	Risk Class	Controls Implemented Using the previous two columns as a guide, decide what actions are necessary to eliminate or minimise the hazards that could lead to an accident, injury or occupational illness or environmental impact. Note: Indicate new risk rating after controls used - that the resulting risk rating must be reduced to between 4 - 6.	Risk Class	Person Responsible
17	Sling Loads to be fitted	load failing	1	 Loads only to be slung and unslung by qualified & competent dogman Dogman to wear hard hat 	6	Dogman
18	Direct crane operator with approved crane signals	 Load make contact with other personnel/ obstructions Wrong directions 	1	 Trained & ticketed dogman to give signals to crane operator by means of two-way communication, whistle or hand signals 	5	Dogman
19	Land loads as per dogman signals	 Crushing fingers Long loads uncontrollable Area the load is required to be handed on, not structurally sound to accept load being landed 	1	 Principle contractor to issue engineers reporting for the structural soundness of are required to use 	5	Operator, Dogman & Principle Contractor
20	Lifting over workers on site/deck	 Object falling onto workers on deck/site 	1	 Dogman to alert personnel on site working under path of load Exclusion one signage to be put in place 	6	Operator & Dogman
21	Using landed load and remove lifting equipment manually	 Fingers being crushed Loads falling off Lifting gear snagging load if dragged out by crane 	1	 Physically take out lifting equipment from under loads 	5	Operator & Dogman
22	Pack-up crane	 Personnel and property damage 	1	Pack up as per generic SWMS005	6	Operator & Dogman

Declaration by Contractors & Workers: This Safe Work Method Statement has been developed in consultation with our employees, has been read, understood & signed by ALL employees and

contractors involved with this specific work activity.

Note: Copies of all training certificates should be made available to the Principal or Head Contractor.

NAME	SIGNATURE		DATE	
INDUCTION OHS CARD #	WORK ACTIVITY	SITE SPECIFIC #		

NAME	SIGNATURE		DATE	
INDUCTION OHS CARD #	WORK ACTIVITY	SITE SPECIFIC #		

NAME	SIGNATURE		DATE
INDUCTION OHS CARD #	WORK ACTIVITY	SITE SPECIFIC #	-

NAME	SIGNATURE		DATE
INDUCTION OHS CARD #	WORK ACTIVITY	SITE SPECIFIC #	

NAME	SIGNATURE		DATE
INDUCTION OHS CARD #	WORK ACTIVITY	SITE SPECIFIC #	

NAME	SIC	GNATURE			DATE	
INDUCTION OHS CARD #	W	/ORK ACTIVITY		SITE SPECIFIC #		

NAME	SIGNATURE			DATE	
INDUCTION OHS CARD #	WORK ACTIVITY		SITE SPECIFIC #		